



**ALL INDIA INSTITUTE OF MEDICAL SCIENCES, BATHINDA**

ਅਖਿਲ ਭਾਰਤੀ ਆਯੁਰ ਵਿਗਿਆਨ ਸੰਸਥਾਨ, ਬਠਿੰਡਾ | ਅਖਿਲ ਭਾਰਤੀ ਆਯੁਰਵਿਗਿਆਨ ਸੰਸਥਾਨ, ਬਠਿੰਡਾ  
(A Central Autonomous Body under the Ministry of Health and Family Welfare, New Delhi)

**DEPARTMENT OF ENGINEERING & ESTATE OFFICE**



No. AIIMS Bathinda/Engg. & Estate/24-25/2008

Dated 30 July 2024

**CALL FOR QUOTATIONS FROM PROSPECTIVE FIRMS**

**Name of the Work: - Epoxy Flooring at Dialysis Ward, OPD First Floor, AIIMS Bathinda**

1. In compliance of the Office Order No. AIIMS/BTI/Estate/OO/2006 dated 30 July 2024, there is a need to publish the quotation document for "Provision of Epoxy Flooring at Dialysis Ward, OPD, First Floor, AIIMS Bathinda" on the Institute Website. The last date of submission of quotation shall be **14 Aug 2024 (Wednesday), 17:00 hrs.** at Department of Engineering & Estate, C Block, 2<sup>nd</sup> Floor, Medical College, AIIMS Bathinda-151001.
2. The BoQ, Scope of Work and Terms & Conditions for the above said work is attached with this notice.
3. The quotation shall be submitted in a sealed envelope duly stamped & signed and "**Quotation for Provision of Epoxy Flooring at Dialysis Ward, OPD, First Floor, AIIMS Bathinda – Dept. of Engineering & Estate**" should be superscribed on the envelopes.
4. Unsealed quotations, quotations received after due date, quotations not superscribed as per Para No. 3 above, unsigned quotations are liable to be rejected. No queries regarding the same shall be entertained in this office.
5. Quotations received through email, fax, telegram etc. shall not be entertained.
6. The decision of AIIMS Bathinda on all matters concerning this work shall be final and binding on the party submitting the quotation.

Sd/-  
Assistant Engineer (Civil),  
AIIMS Bathinda

## **Scope Of the work**

### **(Name of the work:) Epoxy Flooring of Dialysis Unit as per national Hemodialysis guidelines at AIIMS Bathinda.**

1. Providing, transporting and laying 2mm thick Epoxy Polyurethane (EPU) flooring of approved quality and Colour on finished Tiles flooring and walls.
2. Sample must have to be approved by engineer in charge prior to the commencement of the work.
3. Necessary approved adhesive for laying EPU must be used.
4. Cleaning the floor and walls before and after laying of flooring must be carried out by the vendor itself.
5. Approx. area for PU flooring is 4600 sqft. It can vary and payment shall be made as per actual measurement.

## **GENERAL CONDITIONS (CIVIL)**

### **Epoxy Flooring of Dialysis Unit as per national Hemodialysis guidelines at AIIMS Bathinda**

1. Except for the items, for which Particular Specifications are given or where it is specifically mentioned otherwise in the description of the items in the schedule of quantities, the work shall generally be carried out in accordance with the national Hemodialysis guidelines
2. The works to be governed by this contract shall cover delivery and transportation up to destination, safe custody at site, insurance, erection, testing and commissioning of the entire works.
3. For construction works which are likely to generate malba / rubbish, contractor shall dispose of malba, rubbish & other unserviceable materials and wastes at his own cost beyond the premises of AIIMS, Bathinda.
4. The rates quoted by the Contractor are deemed to be inclusive of site clearance, setting out work, profile, establishment of reference bench mark(s), taking spot levels, construction of all safety and protection devices, barriers, preparatory works, working during monsoon, working at all depths, height, lead, lift and location etc. until / unless specified otherwise and any other incidental works required to complete this work. Nothing extra shall be payable on this account. No tools and plants including any special T&P etc. shall be supplied by the Department and the Contractor shall have to make his own arrangements at his own cost. No claim of hindrance (or any other claim) shall be entertained on this account.
5. Materials being used in work shall be conforming to criteria as of Hemodialysis guidelines.
6. Samples for any of items which is to be executed shall be approved by engineer in charge before execution of the work.

**Special Conditions**  
**(Epoxy Flooring of Dialysis Unit as per national Hemodialysis guidelines**  
**at AIIMS Bathinda)**  
**LIQUIDATED DAMAGES**

The successful bidder has to start the work within 15 days of issuance of Letter of Commencement of work and complete the work within the time frame as stipulated by the AIIMS Bathinda, failing which, AIIMS Bathinda will recover Compensation for Delay of work @ .5 % per week or part of the week of delayed of the total amount of work (accepted Tendered Value of work) which may be recovered from Running bill/Performance Security/Security Deposit of the contractor. The total amount of compensation for delay to be paid under this condition shall not exceed 10% (Ten percent) of the Accepted tendered value of work. The said work can also be executed under the Risk and Cost of the Contractor with prior intimation of 15 days based upon the performance of the contractor.

**STATUTORY DEDUCTIONS**

All the statutory deductions towards GST/Income Tax etc. shall be made from the bill/s as applicable as per the prevailing rates under the rules. TDS as applicable will be deducted from each bill of the contractor under the statutory rules of the Union Govt., in respect of Income Tax and other taxes. No claim on account of any other statutory charges for execution of work awarded under this contract will be entertained by AIIMS Bathinda and such charges should be paid by the contractor himself.

**INDEMNIFICATION**

AIIMS Bathinda shall have no liability whatsoever towards the persons deployed by the contractor for the subject of work. The contractor shall keep AIIMS Bathinda indemnified against all losses/damages/liabilities/claims arising out of deployment of the contractor's workers during the period of the contract. Any claim which may arise during the currency of the contract or at any subsequent point of time shall be the sole responsibility of the contractor and AIIMS Bathinda shall in no way be held responsible for it.

**LIABILITY AGAINST LOSS OR DAMAGE TO LIFE OR PROPERTY**

The contractor shall be liable to pay AIIMS Bathinda for any loss/damage caused as a result of theft/pilferage of any property of AIIMS Bathinda from the premises where the staffs of the contractor have been deployed, provided such loss/damage is due to the negligence of the contractor or its deployed manpower which shall be deducted from Security deposit/Performance Guarantee if not paid. The contractor shall also be liable for the consequences of any incident of major/minor injury or accident or death caused to any of its worker arising out of or in the course of his employment under the scope of the contract. AIIMS Bathinda shall not be responsible for any injury or loss of life in respect of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of life shall be the sole responsibility of the contractor. The contractor shall be solely responsible for any damage, injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to AIIMS Bathinda

**Defect liability period:** DLP shall be 01 year from the completion of the work

**Payment terms:** Payment shall be made after completion of the work and verification and measurement of the actual work in measurement books.

**Bill Of Quantiy**

**Name of the work: Epoxy Flooring in Dylisis Unit at 1st Floor Opd Block**

<b>S. No.</b>	<b>Item Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
<b>1</b>	<b>Providing and Laying 2 mmm thick Epoxy polyurethene (EPU) flooring of approved quality and colour on finished tiles flooring and walls with necessary approved adhesive for laying EPU including cleaning the floor before and after laying of flooring as per national hemodialysis guidelines including all transportation charges.</b>	<b>sq ft</b>	<b>4600</b>		
<b>TOTAL</b>					
<u><b>GST 18%</b></u>					
<b>TOTAL AMOUNT WITH GST</b>					