



## **ALL INDIA INSTITUTE OF MEDICAL SCIENCES, BATHINDA**

NEAR GIANI ZAIL SINGH COLLEGE, JODHPUR ROMANA, DABWALI ROAD-151001

### **Invitation of quotations for Provision of Aluminium Partition in Sample Collection Corridor Area at AIIMS Bathinda**

Reference No.: AIIMS Bathinda/Engg. & Estate/25-26/4568

Dated: 14 June 2025

## Notice for Invitation of quotations

**Sealed Quotations** are invited on behalf AIIMS, Bathinda for the subject work at AIIMS Bathinda as per terms & conditions mentioned below. The filled quotations along with all the required documents must reach in the office of the undersigned on or before **25<sup>th</sup> June 2025 (Wednesday), 17:00 hrs. (Date & Time)**. The **Envelope containing the quotation** must be sealed and **super scribed as under**: -

***“Invitation of quotations for Provision of Aluminium  
Partition in Sample Collection Corridor Area at AIIMS  
Bathinda’– Department of Engineering & Estate”***

**The Quotation should be sent to the address: -**

The Executive Director  
AIIMS Bathinda,  
Mandi Dabwali Road,  
Punjab - 151001.

**Terms & Conditions:**

1. The quotations received **after this deadline or unsealed shall not be entertained** under any circumstances whatsoever. In case of postal delay this Institute will not be responsible. The offer submitted by Fax / email shall not be considered and no correspondence will be entertained in this matter.
- (i) AIIMS Bathinda Reserve the right to cancel quotation without any information.
2. Quotations must be in the **enclosed prescribed Performa (BoQ) on the letterhead of the firm duly signed** by the Proprietor/ Partner/ Director or their authorized representative, in case of signing of quotation by the authorized representative letter of authorization must be attached with the quotation.
3. **Make/Model:-**
  - (i) The Vendor has to supply make mentioned in BoQ.
  - (ii) The supplier should supply and installed all the items.
4. Rates must be quoted in Indian rupees. Rates must be inclusive of **all charges** (including Freight charges, taxes, etc.). **No overwriting or cutting** is permitted in the rate. If found, the quotation shall be summarily rejected.
5. The **rates quoted must be valid for 90 days minimum from the date of opening of the quotation** and silence of any tendered on this issue shall be treated as agreed with this condition.
6. **Total cost/amount will be taken in consideration for L1.** Becoming L1 will not be the criteria for awarding of purchase order unless the rates are reasonable & justified.

7. The firm/agency may satisfy the following conditions: -
  - (i) The firm shall have valid GST/Other taxes and IT PAN.
  - (ii) The firm should not be black listed by any Government agency/Department.
8. Quantity may increase or decrease as per the decision of the competent authority of AIIMS Bathinda.
8. **Work Completion period** – within 30 days from Purchase order or as per work order awarded.
9. **Payment Terms:** Payment will be only after satisfactory execution of the work and after inspection by the AIIMS Bathinda. Payment will be done after verification of the work done by the engineering wing. No advance payment shall be admissible.
10. Unsealed quotations, quotations received after due date, quotations not superscribed as mentioned above, unsigned quotations are liable to be rejected. No queries regarding the same shall be entertained in this office. Quotations received through email, fax, telegram etc. shall not be entertained.
11. The decision of AIIMS Bathinda on all matters concerning this work shall be final and binding on the party submitting the quotation.
12. **Defect Liability Period:** DLP shall be of as per warranty of make.
13. To ensure the compliance during the **DLP period, 05% of the amount shall be withheld** from each bill of the contractor and that will be released after completion of the DLP period.
14. If the contractor does not start the work within the scheduled time, the contractor shall be debarred from participating in future tender of the Institute as per the respective clause of the Manual for Procurement of Works.
15. The work shall required to be executed as per the CPWD specifications. Substandard material/ work shall be rejected. Replacement of the same be done within 03 days from the issue of the notice, otherwise the contractor shall be liable to be penalized.
16. **LIQUIDATED DAMAGES:** - The successful bidder must start the work within 7 days of issuance of Letter of Commencement of work and complete the work within the time frame as stipulated by the AIIMS Bathinda, failing which, AIIMS Bathinda will recover Compensation for Delay of work @ .5 % per week or part of the week of delayed of the total amount of work (accepted Tendered Value of work) which may be recovered from bill/Performance Security/Security Deposit of the contractor. The total amount of compensation for delay to be paid under this condition shall not exceed 5 % (Five percent) of the Accepted tendered value of work. The said work can also be executed under the Risk and Cost of the Contractor with prior intimation of 15 days based upon the performance of the contractor.

17. **STATUTORY DEDUCTIONS:** - All the statutory deductions towards GST/Income Tax etc. shall be made from the bill/s as applicable as per the prevailing rates under the rules. TDS as applicable will be deducted from each bill of the contractor under the statutory rules of the Union Govt., in respect of Income Tax and other taxes. No claim on account of any other statutory charges for execution of work awarded under this contract will be entertained by AIIMS Bathinda and such charges should be paid by the contractor himself.

18. **INDEMNIFICATION:** - AIIMS Bathinda shall have no liability whatsoever towards the persons deployed by the contractor for the subject of work. The contractor shall keep AIIMS Bathinda indemnified against all losses/damages/liabilities/claims arising out of deployment of the contractor's workers during the period of the contract. Any claim which may arise during the currency of the contract or at any subsequent point of time shall be the sole responsibility of the contractor and AIIMS Bathinda shall in no way be held responsible for it.

19. **LIABILITY AGAINST LOSS OR DAMAGE TO LIFE OR PROPERTY:** - The contractor shall be liable to pay AIIMS Bathinda for any loss/damage caused because of theft/pilferage of any property of AIIMS Bathinda from the premises where the staffs of the contractor have been deployed, provided such loss/damage is due to the negligence of the contractor or its deployed manpower which shall be deducted from Security deposit/Performance Guarantee if not paid. The contractor shall also be liable for the consequences of any incident of major/minor injury or accident or death caused to any of its worker arising out of or in the course of his employment under the scope of the contract. AIIMS Bathinda shall not be responsible for any injury or loss of life in respect of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of life shall be the sole responsibility of the contractor. The contractor shall be solely responsible for any damage, injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to AIIMS Bathinda.

Sd/-  
Executive Engineer (Civil),  
AIIMS Bathinda

**Check List**

<b>S. No.</b>	<b>Particulars</b>	<b>Whether attached</b>	<b>Remarks</b>
1	GST certificate	YES / NO	
2	PAN Card	YES / NO	
3	Non-Blacklisting Undertaking on letter head	YES / NO	
4	All the documents mentioned above and the quotation document has been signed & stamped	YES /NO	

BOQ					
Name of work : Provision of Aluminium Partition in Sample Collection Corridor Area					
S.No	Description	Unit	Quantity	Rate	Amount
1	Providing and fixing Aluminium work for doors,windows,ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285.Fixing with dash fastners of required dia and size including necessary filling up the gaps at junctions ie,at top,bottom and sides with required EPDM rubber/neoprene gasket etc.Aluminium sections shall be smooth,rust free,straight,mitred and jointed mechanically wherever required including cleat angle,aluminium snap beading for glazing/panelling,C.P.brass/stainless steel screws, all complete as per architectural drawings and directions of Engineer-in-charge.(Glazing,panelling and dash fasteners to be paid separately.)				
	For fixed portion.				
	Powder coated aluminium (Minimum thickness of powder coating 50 micron	Kg	150		
2	For shutters of doors,windows & ventilators including providing and fixing hinges/pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber/neopre gasket required (Fittings shall be paid for separately)				
	Powder coated aluminium(minimum thickness of powder coating 50 micron)	Kg	130		
3	Providing and fixing glazing in aluminium door, window,ventilator shutters and partitions etc, with EPDM rubber/neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in charge.(Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 5mm thickness.				
	With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	Sqm	20		
4	Providing and fixing aluminium round shape handle of outer dia 100 mm with SS screws etc. complete as per direction of Engineer-in-charge				
	Powder coated minimum thickness 50 micron aluminium	Each	12		
5	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	Each	7		
6	Providing and fixing bright finished 100 mm mortice lock with 6 levers without pair of handles of approved quality for aluminium door, with necessary screws etc complete as per direction of Engineer- in-charge.	Each	3		
7	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge				
	Pre-laminated particle board with decorative lamination on both sides	Sqm	14		

8	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.				
	Twin rubber stopper	Each	8		
9	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part 1) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:				
	35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	4		
10	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.				
	In cement mortar	Cum	4		
11	12 mm cement plaster of mix :				
	1:4 (1 cement: 4 fine sand)	Sqm	10		
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade				
	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	Sqm	10		
13	Providing and laying gang saw cut 18 mm thick, mirror polished pre moulded and pre polished machine cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring in road side plazas and similar locations, laid over 20mm thick base of cement mortar 1:4 (1cement : 4 coarse sand) including grouting the joints with white cement mixed with matching pigment, epoxy touch ups etc. complete as per direction of Engineer-in-Charge.				
	With granite stone of area less than 0.50 sqm.	Sqm	2		
<b>Total</b>					
<b>GST@18%</b>					
<b>Total Amonut</b>					