



## ALL INDIA INSTITUTE OF MEDICAL SCIENCES, BATHINDA

NEAR GIANI ZAIL SINGH COLLEGE, JODHPUR ROMANA, DABWALI ROAD-151001

### Invitation of quotations for Construction of Washroom Facility for Female Nursing Officers in all ICUs at AIIMS Bathinda

Reference No.: AIIMS Bathinda/Engg. & Estate/26-27/ 5391

Dated: 04 May 2026

## Notice for Invitation of quotations

**Sealed Quotations** are invited on behalf AIIMS, Bathinda for the subject work at AIIMS Bathinda as per terms & conditions mentioned below. The filled quotations along with all the required documents must reach in the office of the undersigned on or before **18<sup>th</sup> May 2026 (Monday), 17:00 hrs. (Date & Time)**. The **Envelope containing the quotation** must be sealed and **super scribed as under: -**

**“Quotation for Construction of Washroom Facility for  
Female Nursing Officers  
in all ICUs at AIIMS Bathinda –  
Department of Engineering & Estate”**

The Quotation should be sent to the address: -

The Executive Director  
AIIMS Bathinda,  
Mandi Dabwali Road,  
Punjab - 151001.

### Terms & Conditions:

1. The quotations received **after this deadline or unsealed shall not be entertained** under any circumstances whatsoever. In case of postal delay this Institute will not be responsible. The offer submitted by Fax / email shall not be considered and no correspondence will be entertained in this matter.
2. Quotations must be in the **enclosed prescribed Proforma (BoQ) on the letterhead of the firm duly signed** by the Proprietor/ Partner/ Director or their authorized representative, in case of signing of quotation by the authorized representative letter of authorization must be attached with the quotation.
3. The supplier should supply and installed all the items.
4. Rates must be quoted in Indian rupees. Rates must be inclusive of **all charges** (including Freight charges, taxes, etc.). **No overwriting or cutting** is permitted in the rate. If found, the quotation shall be summarily rejected.
5. The **rates quoted must be valid for 90 days minimum from the date of opening of the quotation** and silence of any tendered on this issue shall be treated as agreed with this condition.
6. **Total cost/amount will be taken in consideration for L1.** Becoming L1 will not be the criteria for awarding of purchase order unless the rates are reasonable & justified.
7. The firm/agency may satisfy the following conditions: -
  - (i) The firm shall have valid GST/Other taxes and IT PAN.
  - (ii) The firm should not be black listed by any Government agency/Department.
8. Quantity may increase or decrease as per the decision of the competent authority of



AIIMS Bathinda.

9. **Work Completion period** – within 30 days from Purchase order or as per work order awarded.

10. **Payment Terms:** Payment will be only after satisfactorily execution of the work and after inspection by the AIIMS Bathinda. Payment will be done after verification of the work done by the engineering wing. No advance payment shall be admissible.

11. Unsealed quotations, quotations received after due date, quotations not super scribed as mentioned above, unsigned quotations are liable to be rejected. No queries regarding the same shall be entertained in this office. Quotations received through email, fax, telegram etc. shall not be entertained.

12. The decision of AIIMS Bathinda on all matters concerning this work shall be final and binding on the party submitting the quotation.

13. If the contractor does not start the work within the scheduled time, the contractor shall be debarred from participating in future tender of the Institute as per the respective clause of the Manual for Procurement of Works.

14. The work shall required to be executed as per the CPWD specifications. Substandard material/ work shall be rejected. Replacement of the same be done within 03 days from the issue of the notice, otherwise the contractor shall be liable to be penalized.

15. **LIQUIDATED DAMAGES:** - The successful bidder must start the work within 7 days of issuance of Letter of Commencement of work and complete the work within the time frame as stipulated by the AIIMS Bathinda, failing which, AIIMS Bathinda will recover Compensation for Delay of work @ .5 % per week or part of the week of delayed of the total amount of work (accepted Tendered Value of work) which may be recovered from bill/Performance Security/Security Deposit of the contractor. The total amount of compensation for delay to be paid under this condition shall not exceed 5 % (Five percent) of the Accepted tendered value of work. The said work can also be executed under the Risk and Cost of the Contractor with prior intimation of 15 days based upon the performance of the contractor.

16. **STATUTORY DEDUCTIONS:** - All the statutory deductions towards GST/Income Tax etc. shall be made from the bill/s as applicable as per the prevailing rates under the rules. TDS as applicable will be deducted from each bill of the contractor under the statutory rules of the Union Govt., in respect of Income Tax and other taxes. No claim on account of any other statutory charges for execution of work awarded under this contract will be entertained by AIIMS Bathinda and such charges should be paid by the contractor himself.

17. **INDEMNIFICATION:** - AIIMS Bathinda shall have no liability whatsoever towards the



persons deployed by the contractor for the subject of work. The contractor shall keep AIIMS Bathinda indemnified against all losses/damages/liabilities/claims arising out of deployment of the contractor's workers during the period of the contract. Any claim which may arise during the currency of the contract or at any subsequent point of time shall be the sole responsibility of the contractor and AIIMS Bathinda shall in no way be held responsible for it.

18. **LIABILITY AGAINST LOSS OR DAMAGE TO LIFE OR PROPERTY:** - The contractor shall be liable to pay AIIMS Bathinda for any loss/damage caused because of theft/pilferage of any property of AIIMS Bathinda from the premises where the staffs of the contractor have been deployed, provided such loss/damage is due to the negligence of the contractor or its deployed manpower which shall be deducted from Security deposit/Performance Guarantee if not paid. The contractor shall also be liable for the consequences of any incident of major/minor injury or accident or death caused to any of its worker arising out of or in the course of his employment under the scope of the contract. AIIMS Bathinda shall not be responsible for any injury or loss of life in respect of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of life shall be the sole responsibility of the contractor. The contractor shall be solely responsible for any damage, injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to AIIMS Bathinda.

*Pawan Kumar*

Engineering & Estate Department,  
AIIMS Bathinda

इंजीनियरिंग विभाग / Department of Engineering  
एम्स बठिंडा / AIIMS Bathinda

*[Handwritten signature]*

**Check List**

<b>S. No.</b>	<b>Particulars</b>	<b>Whether attached</b>	<b>Remarks</b>
1	GST certificate	YES / NO	
2	PAN Card	YES / NO	
3	Non-Blacklisting Undertaking on letter head	YES / NO	
4	All the documents mentioned above and the quotation document has been signed & stamped	YES / NO	



*Ramesh Kumar*

## BOQ

### Washroom facility for female Nursing Officers in all ICUs.

S.NO.	Particulars	Unit	Qty	Rate	Amount
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead				
	For thickness of tiles 10 mm to 25 mm	Sqm	10		
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead	Sqm	30		
3	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS: 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	Sqm	10		
4	12 mm cement plaster of mix:				
	1:4 (1 cement: 4 fine sand)	Sqm	10		
5	Cutting holes of required size in brick masonry wall for fixing of exhaust fan including providing and fixing 300 mm dia PVC pipe conforming BIS-12818 and making good the same etc. complete as per direction of Engineer-in-charge.	Each	5		
6	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
	110 mm diameter	RM	30		
7	Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required:				
	(a) White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer	each	5		
8	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
	W.C. pan with ISI marked white solid plastic seat and lid	each	5		
9	Providing and fixing CP Brass 32 mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge	each	5		
10	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :				
	Rectangular shape 453x357 mm	each	5		



*Rohan Kumar*

11	Providing and fixing toilet paper holder				
	C.P. brass	each	5		
12	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.				
	20 mm nominal dia Pipes	metre	20		
13	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931	each	10		
14	Cutting holes up to 15x15 cm in R.C.C. floors and roofs for passing drain pipe etc. and repairing the hole after insertion of drain pipe etc. with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including finishing complete so as to make it leak proof.	each	5		
15	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet :				
	150 mm diameter	each	5		
16	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	20		
17	Brick work with common burnt clay F.P.S ( non modular) bricks of class designation 7.5 in superstructure above plinth level upto floor V level in all shapes and sizes in:				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	10		
18	Finishing walls with textured exterior paint of required shade :				
	New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm	Sqm	10		
19	Finishing walls with Acrylic Smooth exterior paint of required shade :				
	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	Sqm	10		
20	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms	each	5		

*Handwritten signature in blue ink.*

21	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	each	5		
22	Providing and fixing CP Brass Single lever telephonic wall mixer of quality & make as approved by Engineer in charge.	each	4		
23	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour.				
	600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms	each	5		
<b>Total (I)</b>					
<b>GST @ 18%</b>					
<b>GRAND TOTAL</b>					



*Ravans Karmar*